

Coal Technologies incorporating CO<sub>2</sub> Capture – A Program for Research, Development, Demonstration and Deployment

Neville Holt, Stuart Dalton,
George Booras, John Wheeldon
(EPRI)

Presented at the

**3rd DOE/NETL Annual Conference on Carbon Capture and Sequestration** 

May 3-6, 2004

Hilton Alexandria Mark Center, Alexandria, VA



#### **Options for CO<sub>2</sub> Response**

- Conservation (Yes but what about the rest of the world?)
- Renewables (Yes but not enough as a percent of generation)
- Nuclear (Ultimately Yes but questions on waste disposal)
- Adaptation (Probably Yes we usually do)
- Switch from Coal to Natural Gas (Maybe but not enough cheap Natural Gas)
- CO<sub>2</sub> Capture and Sequestration –CCS (Maybe but site specific and costly)

#### Notes:

US Coal Power Plants emit > 2 billion metric tons of  $CO_2/yr$  (~31% of US and 8% of World  $CO_2$  emissions).

1 billion metric tons/yr =  $\sim$ 25 million bpd of supercritical CO<sub>2</sub>



## **Economic Evaluations of SOA Coal Technologies** with CO<sub>2</sub> Capture and Sequestration (CCS)

At current State-of-the Art (SOA) there is no "Silver Bullet" technology for CCS. Technology selection depends on the location, coal and application

- Sequestration is the key technical issue. Probably location and geology dependent
- CO<sub>2</sub> capture adds considerably to Cost of Electricity(COE)
- IGCC/Shift carbon capture least cost for bituminous coals
- IGCC/Shift and PC plants with amine scrubbing are very similar cost for high moisture sub-bituminous Coals
- PC with amine scrubbing least cost for Lignites
- CFBC can handle high ash coals and other low value fuels
- Oxyfuel (O<sub>2</sub>/CO<sub>2</sub> Combustion), Chemical Looping are technologies at developmental stage



# EPRI Economic Estimates for 500 MW Clean Coal Technology Plants without CO<sub>2</sub> Capture - 2003. Bituminous Coal

| Fuel                     | Pittsburgh #8<br>Coal  | Pittsburgh<br>#8 Coal                 | Natural Gas  | Natural<br>Gas |
|--------------------------|------------------------|---------------------------------------|--------------|----------------|
| Technology               | Ultra Supercritical PC | IGCC E-Gas<br>No Spare/<br>With Spare | NGCC         | NGCC           |
| Capacity<br>Factor       | 80                     | 80                                    | 80/65/40     | 80             |
| Fuel Cost<br>\$/MBtu HHV | 1.5                    | 1.5                                   | 3.5          | 4.9            |
| TPC \$/kW                | 1286                   | 1210/1305                             | 440          | 440            |
| COE \$/MWh               | 46.5                   | 46/48                                 | 36.5/40/47.5 | 46.5           |



# **EPRI Economic Estimates for IGCC & PC Plants** without CO<sub>2</sub> Capture – 500 MW with Low Rank Coals

| Technology                        | IGCC E<br>Gas | IGCC Shell<br>No Spare/<br>Spare | PC Sub-<br>critical | IGCC E<br>Gas | PC Sub-<br>critical |
|-----------------------------------|---------------|----------------------------------|---------------------|---------------|---------------------|
| Coal                              | Wyo.<br>PRB   | Wyo. PRB                         | Wyo.<br>PRB         | Lignite       | Lignite             |
| TPC \$/kW                         | 1640          | 1480/1690                        | 1330                | 1830          | 1340                |
| Coal Cost<br>\$/MBtu HHV          | 1.0           | 1.0                              | 1.0                 | 0.5           | 0.5                 |
| COE \$/MWh at 80% Capacity Factor | 54            | 48/54                            | 44                  | 55            | 43                  |



### IGCC for Low Rank Coals - Improvements Needed

- Although entrained flow gasifiers can process all ranks of coal the existing commercial gasifiers all show a marked increase in cost and reduced performance with low rank and high ash coals.
- For slurry fed gasifiers (Texaco, E-Gas) the energy density of slurries with high moisture and/or high ash coal is markedly reduced which increases the oxygen consumption and reduces the gasification efficiency
- For dry coal fed gasifiers (Shell) there is an *energy penalty* (and therefore reduced steam turbine output) *for drying* the high moisture coals to the low moisture content necessary for reliable feeding via lock hoppers and pneumatic conveying
- Although IGCC is closely competitive with PC for bituminous coals the PC capital costs are 300\$-400 \$/kW lower than IGCC for low rank coals and the PC COE is ~20% lower than IGCC
- Potential improvements include slurry preheating & flashing, Coal/CO<sub>2</sub> slurry, coal pump (e.g.Stamet) or other device to deliver as received coal reliably at pressure, Transport gasifier etc



#### Economics of IGCC and USC PC with CO<sub>2</sub> Capture. (Gasification Technologies are not all alike!)

Nominal 450 MW net Plants Pittsburgh #8 Bituminous Coal, All IGCC with spare gasifiers

| Technology                                  | IGCC Texaco<br>Quench | IGCC Texaco<br>Radiant SGC | IGCC<br>E-Gas | IGCC<br>Shell | PC Ultra<br>Supercritical |
|---|-----------------------|----------------------------|---------------|---------------|---------------------------|
| MW<br>no capture                            | 512                   | 546                        | 520           | 528           | 600                       |
| TPC \$/KW<br>no capture                     | 1270                  | 1500                       | 1305          | 1620          | 1235                      |
| COE \$/MWh<br>no capture<br>at 80% CF       | 48.5                  | 53.5                       | 48            | 55.5          | 45                        |
| MW with capture                             | 452                   | 486                        | 442           | 465           | 460                       |
| TPC \$/kW with capture                      | 1620                  | 1900                       | 1870          | 2190          | 2110                      |
| COE \$/MWh with capture                     | 61                    | 67                         | 67            | 73.5          | 75.5                      |
| Avoided<br>Cost of CO <sub>2</sub><br>\$/mt | 18 Sepyright © 20     | 21                         | 29            | 29            | 42                        |

#### Canadian Clean Power Coalition (CCPC) Study for Low Rank Coals with CO<sub>2</sub> Capture (as reported by CCPC- except PC Subbituminous EPRI interpolation)

| Coal                         | Alberta Sub bituminous       | Alberta Sub bituminous   | Saskatch.<br>Lignite         | Saskatch.<br>Lignite | Saskatch.<br>Lignite                              |
|------------------------------|------------------------------|--------------------------|------------------------------|----------------------|---|
| Technology                   | USC PC<br>Amine<br>Scrubbing | Texaco<br>quench<br>IGCC | USC PC<br>Amine<br>Scrubbing | Shell IGCC           | Oxyfuel O <sub>2</sub> /CO <sub>2</sub> Combust'n |
| Net MW                       | 316                          | 437                      | 311                          | 361                  | 373   |
| Coal Cost<br>US \$/MBtu      | 0.48                         | 0.48                     | 0.85                         | 0.85                 | 0.85  |
| TPC<br>US \$/kW              | 2585                         | 2205                     | 2826                         | 2847                 | 3960  |
| COE<br>US\$/MWh<br>at 90% CF | 64                           | 61                       | 74                           | 82                   | 97  |



### IGCC with CO<sub>2</sub> Capture for Sub-bituminous Coals and Lignite - Comments

- Although detailed CO<sub>2</sub> capture studies have not yet been completed, the reduced performance of slurry fed gasifiers (Texaco and E Gas) with high moisture low rank coals will make IGCC less competitive with PC for these coals than was found to be the case for bituminous coals
- In the Canadian CPC study Fluor made several process improvements that reduced the steam consumption for their Econamine (MEA) process (used for post combustion CO<sub>2</sub> removal in PC plants) from 1750 to 1185 Btu/lb of CO<sub>2</sub>.

For Saskatchewan lignite the Shell IGCC COE was greater than for PC with capture (Texaco declined to bid). For the Alberta sub-bituminous coal (similar to PRB) the Texaco IGCC and PC COE's were very similar.



#### The Power Industry needs Technology Options for Responding to Potential CO<sub>2</sub> Legislation 1. Ultra Supercritical (USC) PC and CFBC

- PC designs based on advanced USC materials increase plant efficiency and reduce the cost of capture from flue gas
- Improvements and innovations for CO<sub>2</sub> capture from flue gas need to be investigated and developed
- USC materials can be applied to CFBC thereby extending the range of usable fuels to poorer quality coals, petroleum coke, biomass and wastes.
- CFBC now being offered at 400-600 MW Supercritical.
- Any improvements to CO<sub>2</sub> capture from flue gas could also be applied to CFBC.
- Innovative Combustion technologies such as Oxyfuel, Chemical Looping and Pressurized PC are at an early stage of development but may find application




### The Power Industry needs Technology Options for Responding to Potential CO<sub>2</sub> Legislation 2. IGCC

- To become an Option IGCC needs Deployment Incentives
- Uniquely among the coal technologies IGCC can also find application in co-production of transportation fuels and Hydrogen
- IGCC's advantage over PC for bituminous coals also depends on the specific gasification technology.
- For CO<sub>2</sub> Capture a comprehensive RD&D program for improved performance at high pressure (HP) and with low rank subbituminous and lignite coals is needed
- For Hydrogen production and maximum CO<sub>2</sub> capture high pressure single stage entrained quench gasifiers preferred.
- Gasifiers that produce some CH<sub>4</sub> have higher gasifier efficiency and lower O<sub>2</sub> consumption but reduce the achievable CO<sub>2</sub> capture via the Shift. However if 75% CO<sub>2</sub> capture is acceptable then HP two stage entrained or fluid bed gasifiers may be more efficient and economic




## Effect of Carbon Tax on Cost of Electricity for Various Technologies – Bituminous Coal






### Effect of Carbon Tax on Cost of Electricity for Various Technologies – PRB Coal






#### Combined Effect of Carbon Tax on Emissions & Capture Credit on Cost of Electricity for Various Technologies

#### - Bituminous Coal





# Combined Effect of Carbon Tax on Emissions & Capture Credit on Cost of Electricity for Various Technologies - PRB Coal





### **Effect of Carbon Taxes on Fuel and Technology Selection**

- Main issue is with the existing power plants. U.S. has 320 GW of coal power plants but only ~100GW have FGD.
- The paid off capital on most US coal plants is a great economic advantage. Only at a Carbon tax of tax ~200\$/mt is their COE up to that of a new IGCC with capture and sequestration. They will probably be kept going as long as possible even if they have to add FGD and SCR and Hg removal. If additional capital of 500\$/kW on existing coal plants is required to meet "Clear Skies" the crossover for new coal with capture is still over 150\$/mt of C.
- With NG @ 6\$/MBtu new NGCC with CO<sub>2</sub> venting is lower COE than new IGCC with CCS until the C tax is ~170\$/mt.
- If the purpose of a C tax is to reduce CO<sub>2</sub> emissions and the proceeds were used as credit for technologies with CO<sub>2</sub> capture then capture and sequestration technologies (particularly IGCC) would compete more readily (at lower C tax 70-100\$/mt) with existing coal



#### Future Coal Generation and CCS – Some Issues and Observations

- Does CO<sub>2</sub> Sequestration work? Where ? For how long?
- Can Natural Gas supplant Coal for US Power Generation?
- New Coal Generation will be required under most fuel price scenarios. However CCS costs add~40-50% to COE for IGCC and ~80-90% for PC with bituminous coals.
   Is this going to be acceptable? Can it be significantly reduced?
- The paid off capital on most US coal plants is a great economic advantage. Even with adding FGD,SCR and Hg removal and a large C tax their COE would be much less than new coal. They will probably be kept going as long as possible (See EIA AEO 2004). Question/Issue - How can CO<sub>2</sub> emissions be reduced from existing power plants?
- Significant (>50%) CO<sub>2</sub> reductions at new and existing coal plants can only be achieved with CCS.
   Question/Issue - Could Carbon tax proceeds be used to support the costs of CCS?



#### Coal Technologies for CO<sub>2</sub> Capture and Sequestration (CCS) – Needs

- US CO<sub>2</sub> Policy uncertain. Several legislative proposals. Continued evaluation and analysis of alternatives needed.
- Need Techno-Economic information on Technology Options (buy coal and region) to inform the policy formulation
- Preferred technology depends on the coal, location and application.
- A comprehensive R&D, Demonstration and Deployment program is required to reduce CCS costs for all coal technologies
  - IGCC Deployment Incentives, HP design, low rank coal
  - USC materials, post combustion capture (apply to CFBC)
  - Innovative technologies
- Need better standardized and optimized designs
- Need continual update of techno-economic evaluations as new/improved options emerge to ensure best current information is available to inform policy

